



3527 Branch Rd
Princeton, MN 55371

PROPOSAL


DATE
9/19/2023

PRESENTED TO
Princeton Public Utilities 907 1st Street Princeton, MN 55371

PROJECT

DESCRIPTION	QTY	Unit Meas...	UNIT PRICE	TOTAL
<p>3rd Ave Hydrant Disconnection</p> <p>Remove hydrant at old well site and cap 10" watermain at next hydrant tee.</p> <p>Includes the following:</p> <ul style="list-style-type: none"> -Complete removal of the hydrant and valve box riser at the old well site. The valve is to remain in place, but remain closed to keep infiltration out of the abandoned pipe. -Remove and dispose of necessary bituminous to excavate the tee for the next hydrant on 3rd St. Cut a section of the 10" main out to allow a cap to be installed on the tee. Cap the abandoned 10" to keep infiltration out. Backfill and place class 5 on excavated area. <p>Excludes:</p> <ul style="list-style-type: none"> -Bituminous patching. -Removal/ and or installation of any items not specified above. -Dewatering. 	1	LS	5,250.00	5,250.00
Thank you for this opportunity. Please call with questions.				

Proposal Prepared by Paul Johnson
763-389-2827 Office
763-286-3913 Cell
paul@westbranchconstruction.com

Presented By 
Paul Johnson, President



3527 Branch Rd
Princeton, MN 55371

PROPOSAL

DATE
9/19/2023

PRESENTED TO
Princeton Public Utilities 907 1st Street Princeton, MN 55371

PROJECT

DESCRIPTION	QTY	Unit Meas...	UNIT PRICE	TOTAL
Quote valid for 15 days without a scheduling commitment. Does not include any allowance for winter work or work during spring load restrictions. Sales Tax			7.375%	0.00
Thank you for this opportunity. Please call with questions.				

Proposal Prepared by Paul Johnson
763-389-2827 Office
763-286-3913 Cell
paul@westbranchconstruction.com

Presented By

Paul Johnson, President