

Frontline Warning Systems

Project Estimate

Frontline Plus Fire & Rescue
 DBA/Frontline Warning Systems
 8004 Aetna Avenue NE
 Monticello, MN 55362

Phone # 763-295-3650 frontlineplus@tds.net
 Fax # 763-295-3650 www.frontlinewarningsystems.com

Date
3/15/2024

Name / Address
City of Princeton 705 No. 2nd Ave Att; Accounts Payable Princeton, MN 55371

Terms	Due Date	REP Contact	FOB
Net 20 Days.	4/30/2024	AG	

Item	Description	Qty	Cost	Total
VORTEX/R4	This quote is an itemized proposal for a new Outdoor Warning Siren in any City, Municipality, or Township in Minnesota. This is Promotional Pricing and valid through 4/30/2024. Equipment: VORTEX/R4 Electronic Outdoor Warning Siren; Rotating siren rated at 129dBc @ 100ft and 70dBc @ 6000ft (Est). 4-400watt speaker drivers, ESC2030 Controller, 5a 120v AC battery charger (temperature compensated), motherboard, amplifiers factory installed in Type I aluminum cabinet.	1	19,000.00	19,000.00T
VC2030NV	One-Way VHF High Band Narrow Band Radio Controller for County and Local Activation. This Radio can be activated in Multiple ways from the County to ensure complete redundancy and is also compatible to be added to the County Status Monitoring System for Outdoor Warning Sirens. This Radio Package will also have the ability to be set off Locally by the City but specifics vary for each municipality/county.	1	1,800.00	1,800.00T
POLE TOP BRACKET	VPTB #01-0411446-00. Pole Top Mounting Bracket.	1	800.00	800.00T
VORTT	Vortex & OA series Two-tone sequential option (Steady & Cancel Functions only) or upgrade to Two-Way Radio	0	600.00	0.00T
Installation	Installation: Siren installation. Frontline to deliver, strip and dress pole. Place pole 7.5 to 10ft deep in approved location; digging conditions and access conditions apply.	1	3,000.00	3,000.00T
Materials	Materials as required for installation; conduit, copper, hardware, etc	1	790.00	790.00T
DCM0055	Interstate Battery DCM0055, 12v 55aH	2	205.00	410.00T
SHIPPING	Freight Shipping	1	550.00	550.00T
55ft Class II Pole	55ft Class II Pole (Optional)	0	3,800.00	0.00T
SOLAR POWER	Two (2) 80 Watt Solar Power Panels; replaces incoming AC power (Optional)	0	1,800.00	0.00T

Quote only; subject to availability and terms listed above.	Subtotal
	Sales Tax (0.0%)
	Total

Frontline Warning Systems

Project Estimate

Frontline Plus Fire & Rescue
 DBA/Frontline Warning Systems
 8004 Aetna Avenue NE
 Monticello, MN 55362

Phone # 763-295-3650 frontlineplus@tds.net
 Fax # 763-295-3650 www.frontlinewarningsystems.com

Date
3/15/2024

Name / Address
City of Princeton 705 No. 2nd Ave Attn: Accounts Payable Princeton, MN 55371

Terms	Due Date	REP Contact	FOB
Net 20 Days.	4/30/2024	AG	

Item	Description	Qty	Cost	Total
Standard Warranty	<p>Terms: Whelen Standard Warranty: Years 1 & 2: Full parts coverage Years 3 - 5: Full parts coverage minus \$125 deductible. Exclusions apply. See warranty documentation</p> <p>Terms: 50% due within 30 days of order. Balance will be invoiced (NET30) once installation is completed. Installation will be coordinated with others in the area, in no event will installation occur beyond Sept 30, 2024. Sirens will be ordered in groups on a bi-weekly basis. Estimated production is 10 weeks. To proceed with order; please sign a copy of this estimate and return to Frontline Warning Systems at Support@Frontlinewarningsystems.com, or fax to 763-295-3650. A Installation Representative will then coordinate activation methods, site location and delivery with the user. A purchase order or requisition may also be issued. Installation includes standard dirt/soil locations within 20ft from paved, crushed rock, or concrete road or parking lot with no other obstacles. Any excavation that takes longer than 1.5 hours will be charged at \$300/hr additional and such instances occur from sand, heavy rocks or abandoned services. Normal digging takes 20-30 minutes. Selected site must have good southern exposure for solar array.</p>	1	0.00	0.00T

Quote only; subject to availability and terms listed above.		Subtotal	\$26,350.00
		Sales Tax (0.0%)	\$0.00
		Total	\$26,350.00